# APPENDIX C:
# BMP Outcome Category Matrix

## BMP Outcome Category Matrix

● = Recommended BMP Application but not limited to

| BMP | PAGE | BMP OUTCOME CATEGORY | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | | Keep Water From Work Area | Reduce Potential for Soil Erosion | Filter / Perimeter Protection | Settling | Reduce Water Velocity / Erosive Forces | Containment | Habitat Protection / Maintenance | Reduce Potential for Contaminants Falling Into Water |
| AQUA BARRIER | 2.20 | ● | | | | | | | |
| BACK OF SLOPE PLANTING | 2.23 | | ● | | | ● | | | |
| COFFERDAM | 2.25 | ● | | | | | | | |
| COIR FABRIC | 2.28 | | | | | ● | | ● | |
| COIR LOG | 2.30 | | | ● | ● | ● | | ● | |
| CONCRETE CONTAINMENT (1) | 2.33 | | | | | | ● | | |
| CONCRETE CONTAINMENT (2) | 2.36 | | | | | | ● | | |
| CONSTRUCTION ACCESS ROAD | 2.38 | | ● | | | | | | |
| CONTINUOUS BERM | 2.41 | | | ● | ● | ● | | | |
| CURB INLET SEDIMENT TRAP | 2.44 | | | ● | ● | | | | |
| DEWATERING | 2.49 | ● | | | | | | | |
| DIAPER NETTING | 2.51 | | | | | | | | ● |
| DITCH LINING | 2.53 | | ● | | | ● | | | |
| DIVERSION BERM | 2.55 | ● | | | | | | | |
| DIVERSION CHANNEL | 2.57 | ● | | | | | | | |
| DUST CONTROL | 2.60 | | ● | | | | | | |
| EXCELSIOR FILLED LOG | 2.62 | | | ● | ● | ● | | ● | |
| FILTER FABRIC | 2.64 | | ● | ● | ● | | | | |
| GRASS LINED CHANNEL | 2.66 | | ● | | | ● | | | |
| GRAVEL FILLED SUMP | 2.70 | | | ● | | | | | |
| HALF ROUND FILTER | 2.71 | | | ● | | | | | |
| HAND SEEDING | 2.73 | | ● | | | ● | | ● | |
| HYDROSEEDING | 2.75 | | ● | | | ● | | ● | |
| INLET PROTECTION | 2.77 | | | ● | | | | | |
| KIMBLE FILTER PIPE | 2.84 | | | ● | | | | | |
| LARGE WOODY MATERIAL | 2.86 | | | | | ● | | ● | |
| LIVE STAKING | 2.91 | | ● | | | ● | | ● | |
| MULCHING | 2.95 | | ● | | | ● | | | |
| PLASTIC COVERING | 2.97 | ● | ● | | | | | | |
| PLYWOOD WORK PLATFORM | 2.99 | | | | | | | | ● |

## BMP Outcome Category Matrix

= Recommended BMP Application but not limited to

| BMP | PAGE | BMP OUTCOME CATEGORY | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | | Keep Water From Work Area | Reduce Potential for Soil Erosion | Filter / Perimeter Protection | Settling | Reduce Water Velocity / Erosive Forces | Containment | Habitat Protection / Maintenance | Reduce Potential for Contaminants Falling Into Water |
| RIP RAP | 2.101 | | | | | ● | | | |
| ROCK CHECK DAM | 2.103 | | | | ● | ● | | | |
| SANDBAG | 2.107 | ● | | | ● | ● | | | |
| SEDIMENTATION SUMP | 2.111 | | | | ● | | | | |
| SILT FENCE | 2.112 | | | ● | ● | ● | | | |
| SILT MAT | 2.115 | | | ● | ● | ● | | | |
| SILTATION POND/SETTLING TANK | 2.117 | | | | ● | | | | |
| SOIL STABILIZATION (Blankets/Matting) | 2.120 | | ● | | | | | | |
| STRAW BALE BARRIER (1) | 2.125 | | | ● | ● | ● | | | |
| STRAW BALE BARRIER (2) | 2.128 | | | ● | ● | ● | | | |
| STRAW BALE BARRIER (3) | 2.133 | | | ● | ● | ● | | | |
| STRAW LOG | 2.136 | | | ● | ● | ● | | | |
| STREAM BANK STABILIZATION | 2.139 | | | | | ● | | | |
| STREAM BYPASS | 2.140 | ● | | | | | | | |
| STREAMBED GRAVEL | 2.144 | | | | | | | ● | |
| SURFACE ROUGHENING | 2.146 | | ● | | | ● | | | |
| SWEEPING | 2.150 | | ● | | | | | | |
| TEMPORARY SEDIMENT TRAP | 2.153 | | | | ● | | | | |
| TRIANGULAR SILT DIKE | 2.156 | | | | ● | ● | | | |
| TURBIDITY CURTAIN | 2.160 | | | | ● | ● | | | |
| VACTORING | 2.164 | ● | | | | | ● | | |
| VEGETATIVE BUFFER | 2.166 | | ● | | | ● | | | |
| WASHED ROCK | 2.168 | | | ● | | | | | |